BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Metalling of roads & Construction of drains & Culverts at Narayanswamy layout 1st & 2nd cross Abbigere, in Shettyhalli Sub-Division, Ward No-12, Under 22.75% grant

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, complete as per specifications.	Cum	725.20	127.2	Rupees One Hundred Twenty Seven and Twenty Paise Only
2	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	36.40	109.18	Rupees One Hundred Nine and Eighteen Paise Only
3	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	3.78	3153.5	Rupees Three Thousand One Hundred Fifty Three and Fifty Paise Only
4	Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	15.12	2776.14	Rupees Two Thousand Seven Hundred Seventy Six and Fourteen Paise Only
5	Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	1.68	3845.68	Rupees Three Thousand Eight Hundred Forty Five and Sixty Eight Paise Only
6	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Cum	25.20	57.134	Rupees Fifty Seven and Thirteen Paise Only

Technical Manager-2
KMDL, BBMP, Bangalore
Signature of the Contractor

Executive Engineer

7	Providing and [illegible]ment concrete using 20mm and down size granite je[illegible]ady mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-15 (1:2:4) for raft foundation, column footing, main and secondary beams. complete as per specifications.	Cum	5.80	4386.28	Rupees Four Thousand Three Hundred Eighty Six and Twenty Eight Paise Only
8	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Q	6.96	5031.14	Rupees Five Thousand Thirty One and Fourteen Paise Only
9	Providing, laying spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screeing/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Material (Refer table 400-7, 8&9) Using Screening Crushable type such as Moorum or Gravel Grading-II (Manual) No.141 / complete as per specifications.	Cum	310.80	1245.5	Rupees One Thousand Two Hundred Forty Five and Fifty Paise Only
10	Providing, laying spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading inl uniform thickness, hand packing, rolling with 3 wheeled steel / ibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requistie type of screeing /binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Mateial complete as per specifications.	Cum	207.20	1414.04	Rupees One Thousand Four Hundred Fourteen and Four Paise Only
11	Carriage of mixed materials 10 Kms, complete as per specifications.	Cum	518.00	79.24	Rupees Seventy Nine and Twenty Three Paise Only
12	Conveying the excavaed earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete as per specifications.	Cum	706.00	71.34	Rupees Seventy One and Thirty Three Paise Only

Technical Manager-2
KRIDL, BBMP, Bangalore
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,